



HLE STRYKR

The Transit-chassis shuttle. Fourteen passengers, no CDL on most routes, and a body built like the big ones.



High Level Enterprises, Inc.

Wakarusa, Indiana

highlevelbus.com

574-343-2150

sales@highlevelbus.com

Floor plans, photos and walkaround video for this model: highlevelbus.com/models/strykr. Every figure here is published on the compare page and is current as of September 2026. Confirm the exact build with your dealer before a purchase order.

Capacity

Passenger capacity	Up to 14 passengers · up to 6 wheelchair positions
Model sizes	HLE-21 – HLE-24
Luggage options	Rear compartment · overhead · interior rack
Passenger seat width	17.5 in standard · 15.5 in option · 19 in upgrade
Seat spacing	26 – 42 in, typically 31 – 34 in by floor plan

Chassis

Chassis options	Ford Transit T-350
Engine	Ford 3.5L gas
GVWR	9,950 – 11,000 lb
Fuel options	Gas · Propane · CNG
Fuel tank capacity	25.1 gal standard · 31 gal extended range
Alternator	250 A

Dimensions

Wheelbase	138 – 156 in
Body length	150 – 187 in
Body width (mirrors excluded)	84 in
Interior width	80 in, inside wall to inside wall
Overall height	118 in without roof-mounted A/C — a roof-mounted A/C adds to this
Interior standing height	Raised floor 82 in · standard floor 86.5 in
Entry steps	3-step entry (raised floor) · 2-step entry (standard floor)
Step riser / run	Raised floor 11 in rise × 11 in run · standard floor 8 in × 8 in
Ground to first step	11.5 in
Aisle width	22 in (seat to seat, without armrests)



Accessibility	
Entry door width	36 in rough opening (33 in clear) · 42 in rough opening optional
Entry door opening height	82 in (floor to opening)
Wheelchair lift	Braun 800 – 1,000 lb · platform 34×51, 34×54, 37×51 or 37×54 in
Climate	
Air conditioning capacity	55,000 – 100,000 BTU
Construction	
Body structure	1 in × 1.5 in welded steel cage, fully powder-coated
Sidewalls	Pressure-laminated one-piece, bonded to the steel structure — no beltline seam
Roof	One-piece Impact Guard (grade IG03), fiberglass-reinforced polypropylene
Sub-floor	PerformMAX 500 with Ovation overlay
Insulation	1 in closed-cell EPS foam board, cut to fill each wall cavity · insulation R-3.9
Wiring	Custom-built wiring and harnesses per HLE brand · Amphenol / Molex marine-grade connectors
Leak test	Every bus rain-tested before delivery, with an inspector riding inside
Warranty and testing	
Warranty	3yr/36K bumper-to-bumper · 5yr/100K structural body · 7-year subfloor
Air conditioning warranty	By installed system — Spheros up to 5 years / unlimited miles · Trans/Air 2 years standard, extensions available
Testing	FMVSS compliant · FTA Altoona test in progress

How it is built

Feature	What it means
Steel cage	Welded 16-gauge steel tube, fully powder-coated, built directly on the chassis. Doubled roof tube, welded rear-wall bracing, welded skirt.
One-piece sidewall	A single pressure-laminated panel from roofline to skirt, bonded to the steel. No beltline seam, no floor-line seam.
Impact Guard roof	One-piece composite roof, reinforced through the panel and around the radius. It folds without cracking; ask your dealer for the sample.
PerformMAX 500 sub-floor	5/8-inch composite panel that sheds water instead of soaking it up, on laser-cut steel crossmembers. Warranted seven years.
Foam insulation	Closed-cell EPS board cut to fill every wall cavity to full depth and glued in place.
In-house wiring	Every harness built in Wakarusa with marine-grade sealed connectors and full loom. No butt connectors, no tap splices.
Rain-tested, every bus	Fifteen minutes minimum under full spray with an inspector inside, then a 25-mile road test, before delivery.

What is covered, in writing

Coverage	Term
Bumper-to-bumper (body and conversion)	3 years / 36,000 miles
Body structure, framing, roof, sidewalls, floor structure, body electrical, paint workmanship	5 years / 100,000 miles
PerformMAX 500 sub-floor	7 years / unlimited miles
Air conditioning	By installed system: Spheros up to 5 years / unlimited miles; Trans/Air 2 years standard
Chassis	Chassis manufacturer's warranty, in full

Effective September 2026. Original owner. Nothing in an HLE warranty prorates. Full documents at highlevelbus.com/why-hle/warranty-testing. Overall length is published per floor plan at highlevelbus.com/floor-plans.